



Huntingdonshire Level 2 Strategic Flood Risk Assessment Site Summary

Site CfS:276

Final Draft Report

Prepared for
Huntingdonshire District
Council

Date
November 2025

Document Status

Issue date	6 November 2025
Issued to	Frances Schulz
BIM reference	JFI-JBA-XX-XX-RP-EN-0044
Revision	P03
Prepared by	Mike Williamson BSc MSc CGeog FRGS EADA Principal Analyst
Reviewed by	Laura Thompson BSc FRGS Analyst
Authorised by	Paul Eccleston BA CertWEM CEnv MCIWEM C.WEM Technical Director

Carbon Footprint

The format of this report is optimised for reading digitally in pdf format. Paper consumption produces substantial carbon emissions and other environmental impacts through the extraction, production and transportation of paper. Printing also generates emissions and impacts from the manufacture of printers and inks and from the energy used to power a printer. Please consider the environment before printing.

Accessibility

JBA aims to align with [governmental guidelines on accessible documents](#) and [WGAG 2.2](#) AA standards, so that most people can read this document without having to employ special adaptation measures. This document is also optimised for use with assistive technology, such as screen reading software.

Contract

JBA Project Manager	Mike Williamson
Address	Phoenix House, Lakeside Drive, Centre Park, Warrington, WA1 1RX
JBA Project Code	2022s1322

This report describes work commissioned by Huntingdonshire District Council by an instruction via email dated 21 July 2025. The Client's representative for the contract was Frances Schulz of Huntingdonshire District Council. Mike Williamson of JBA Consulting carried out this work.

Purpose and Disclaimer

Jeremy Benn Associates Limited ("JBA") has prepared this Report for the sole use of Huntingdonshire District Council in accordance with the Agreement under which our services were performed.

JBA has no liability for any use that is made of this Report except to Huntingdonshire District Council for the purposes for which it was originally commissioned and prepared.

No other warranty, expressed or implied, is made as to the professional advice included in this Report or any other services provided by JBA. This Report cannot be relied upon by any other party without the prior and express written agreement of JBA.

JBA disclaims any undertaking or obligation to advise any person of any change in any matter affecting the Report, which may come or be brought to JBA's attention after the date of the Report.

The methodology adopted and the sources of information used by JBA in providing its services are outlined in this Report. The work described in this Report was undertaken between 21 July 2025 and 6 November 2025 and is based on the conditions encountered and the information available during the said period. The scope of this Report and the services are accordingly factually limited by these circumstances.

The conclusions and recommendations contained in this Report are based upon information provided by others and upon the assumption that all relevant information has been provided by those parties from whom it has been requested and that such information is accurate.

Acknowledgements

We would like to thank the Environment Agency, Cambridgeshire County Council for their assistance with this work.

Copyright

© Jeremy Benn Associates Limited 2025

Contents

1	Background	1
1.1	Site CfS:276	1
2	Flood risk from rivers and sea	5
2.1	Existing risk	5
2.2	Flood risk management	8
2.3	Impacts from climate change	9
2.4	Historic flood incidents	12
2.5	Emergency planning	13
2.6	Observations, mitigation options, site suitability, sequential approach to development management - fluvial and tidal	14
3	Flood risk from surface water	15
3.1	Existing risk	15
3.2	Impacts from climate change	18
3.3	Observations, mitigation options, site suitability, sequential approach to development management - surface water	21
4	Cumulative impacts assessment and high risk catchments	22
4.1	Level 1 cumulative impacts assessment	22
5	Groundwater, geology, soils, SuDS suitability	23
6	Residual risk	26
6.1	Potential blockage / breach	26
6.2	Flood risk from reservoirs	26
7	Overall site assessment	28
7.1	Can part b) of the exception test be passed?	28
7.2	Recommendations summary	28
8	Licencing	29

List of Figures

Figure 1-1: Existing site location boundary	2
Figure 1-2: Aerial photography	3
Figure 1-3: Topography	4
Figure 2-1: Existing risk	5
Figure 2-2: Flood depths for 1% AEP undefended flood event	6
Figure 2-3: Flood velocities for 1% AEP undefended flood event	7
Figure 2-4: Flood hazard for 1% AEP undefended flood event	8
Figure 2-5: Natural Flood Management (NFM) potential mapping	9
Figure 2-6: Flood depths for 1% AEP undefended flood event +19% (central climate change allowance)	10
Figure 2-7: Flood velocities for 1% AEP undefended flood event +19% (central climate change allowance)	11
Figure 2-8: Flood hazard ¹ for 1% AEP undefended flood event +19% (central climate change allowance)	12
Figure 2-9: Recorded historic flood events onsite and around the site	13
Figure 2-10: EA Flood Warning Areas and Flood Alert Areas	14
Figure 3-1: Surface water flood extents (NaFRA2 - Risk of Flooding from Surface Water map)	16
Figure 3-2: Medium risk event surface water flood depths (Third generation - Risk of Flooding from Surface Water map)	17
Figure 3-3: Medium risk event surface water flood hazard (Third generation - Risk of Flooding from Surface Water map)	18
Figure 3-4: Low risk event surface water flood extent, as a proxy for the medium risk event plus climate change (NaFRA2 - Risk of Flooding from Surface Water map)	19
Figure 3-5: Low risk event surface water flood depths, as a proxy for the medium risk event plus climate change (Third generation - Risk of Flooding from Surface Water map)	20
Figure 3-6: Low risk event surface water flood hazard, as a proxy for the medium risk event plus climate change (Third generation - Risk of Flooding from Surface Water map)	21
Figure 5-1: JBA 5m Groundwater Emergence Map	23
Figure 5-2: Soils and geology	25
Figure 6-1: EA Reservoir Flood Map	27

List of Tables

Table 2-1: Existing flood risk based on percentage area of site at risk	5
Table 2-2: Modelled climate change allowances for peak river flows for the Upper and Bedford Ouse management catchment	9
Table 3-1: Existing surface water flood risk based on percentage area at risk using the NaFRA2 RoFSW map	15
Table 5-1: Groundwater Hazard Classification	24

1 Background

This is a Level 2 Strategic Flood Risk Assessment (SFRA) site screening report for Local Plan Site CfS:276. The content of this report assumes the reader has already consulted the 'HDC Level 1 SFRA' (2024) and read the 'HDC Level 2 SFRA Main Report' (2025) and is therefore familiar with the terminology used in this report.

1.1 Site CfS:276

- Location: Huntingdon Racecourse
- Existing site use: racecourse and associated commercial buildings, predominantly greenfield
- Existing site use vulnerability: less vulnerable
- Proposed site use: commercial
- Proposed site use vulnerability: less vulnerable
- Site area (ha): 68.67
- Watercourse: Alconbury Brook, ordinary watercourses
- Environment Agency (EA) model: Lower Ouse 2015 (Alconbury Brook)
- Summary of requirements from Level 2 SFRA scoping stage:
 - Assessment of fluvial flood depths, velocities and hazards
 - Assessment of surface water flood extent, depths and hazards
 - Assessment of all other sources of flood risk




Figure 1-1: Existing site location boundary




Figure 1-2: Aerial photography




Figure 1-3: Topography

2 Flood risk from rivers and sea

2.1 Existing risk

2.1.1 Flood Map for Planning and functional floodplain

Based on the EA's Flood Map for Planning (accessed July 2025) and Flood Zone 3b (functional floodplain), as updated in this Level 2 SFRA, the percentage areas of the site within each flood zone are stated in Table 2-1 and can be viewed on Figure 2-1. This version of the Flood Map for Planning does not consider flood defence infrastructure (Section 2.2) or the impacts of climate change (Section 2.3).

The majority of the site is modelled to be within Flood Zone 3b (functional floodplain). Less vulnerable development is not permitted in Flood Zone 3b. Flood Zone 3b in this location is based on the Flood Map for Planning 3.3% AEP defended fluvial event.

Table 2-1: Existing flood risk based on percentage area of site at risk

Flood Zone 1 (% area)	Flood Zone 2 (% area)	Flood Zone 3a (% area)	Flood Zone 3b (% area)
8	9	2	81




Figure 2-1: Existing risk

2.1.2 Fluvial undefended model outputs (Lower Ouse 2015 (Alconbury Brook))

Figures 2-2, 2-3, and 2-4 show the modelled flood depths, velocities, and hazards for the 1% AEP undefended event respectively. Risk is modelled to be significant across the majority of the site.




Figure 2-2: Flood depths for 1% AEP undefended flood event




Figure 2-3: Flood velocities for 1% AEP undefended flood event




Figure 2-4: Flood hazard¹ for 1% AEP undefended flood event

2.2 Flood risk management

2.2.1 Flood defences

The site does not benefit from any formal engineered flood defences, according to the EA's spatial flood defences dataset.

2.2.2 Working with Natural Processes

The EA's Working with Natural Processes (WwNP) dataset has been interrogated to identify opportunities for Natural Flood Management (NFM) to reduce flood risk to the site and surrounding areas. These areas are shown in Figure 2-5. Note, the WwNP mapping is broadscale and indicative, therefore further investigation will be required for any land shown to have potential for WwNP. There are large areas of land surrounding and upstream of the site with potential for various WwNP measures, such as tree planting and floodplain reconnection.

¹ Fluvial hazard ratings based on Table 4 of the SUPPLEMENTARY NOTE ON FLOOD HAZARD RATINGS AND THRESHOLDS FOR DEVELOPMENT PLANNING AND CONTROL PURPOSE – Clarification of the Table 13.1 of FD2320/TR2 and Figure 3.2 of FD2321/TR1. May 2008.




Figure 2-5: Natural Flood Management (NFM) potential mapping

2.3 Impacts from climate change

2.3.1 Fluvial

The EA's SFRA guidance states that SFRAs should assess the central allowance for less, more, highly vulnerable, and water compatible development. The higher central allowance should be assessed for essential infrastructure. The impacts of climate change on flood risk from Alconbury Brook have been modelled using the Lower Ouse 2015 (Alconbury Brook).

With consideration of the EA's SFRA guidance, the latest central and higher central climate change allowances have been modelled in this Level 2 SFRA as shown in Table 2-2.

Table 2-2: Modelled climate change allowances for peak river flows for the Upper and Bedford Ouse management catchment

Return period (AEP event)	Central allowance 2080s (% increase)	Higher central allowance 2080s (% increase)
2% (in absence of 3.3%)	19%	30%
1%	19%	30%
0.1%	Model instabilities. Could not run	

Figures 2-6, 2-7, and 2-8 show the modelled flood depths, velocities, and hazards for the 1% AEP undefended event plus the central climate change allowance (+19%) respectively. Risk is shown to increase across the site.




Figure 2-6: Flood depths for 1% AEP undefended flood event +19% (central climate change allowance)




Figure 2-7: Flood velocities for 1% AEP undefended flood event +19% (central climate change allowance)




Figure 2-8: Flood hazard¹ for 1% AEP undefended flood event +19% (central climate change allowance)

2.4 Historic flood incidents

The EA's Historic Flood Map (HFM) and Recorded Flood Outlines (RFO) datasets have been considered and mapped in Figure 2-9 which shows several historic flood events having impacted the site, namely, an event in March 1947, source unknown; and in Easter 1998, source unknown.




Figure 2-9: Recorded historic flood events onsite and around the site

2.5 Emergency planning

2.5.1 Flood warning

The EA operates a Flood Warning Service for properties located within a Flood Warning Area (FWA) for when a flood event is expected to occur. The whole risk area of the site is located within a FWA, namely the Alconbury Brook at Hamerton, Alconbury Weston, Alconbury, Little Stukeley and Brampton FWA.

Flood alerts may be issued before a flood warning for properties located within a Flood Alert Area (FAA) to provide advance notice of the possibility of flooding. A flood alert may be issued when there is less confidence that flooding will occur in a FWA. The risk area of the site is also located within a FAA, namely the Alconbury Brook in Cambridgeshire FAA.




Figure 2-10: EA Flood Warning Areas and Flood Alert Areas

2.5.2 Access and escape routes

Based on available information, safe access and escape routes will be challenging to achieve. The current main access route from the A141 is shown to be at significant risk and cannot therefore be considered safe in a flood event.

2.6 Observations, mitigation options, site suitability, sequential approach to development management - fluvial and tidal

- Observations:
 - A large proportion of the site is within the functional floodplain and therefore cannot be developed for less vulnerable purposes.
- Mitigation:
 - The site should be left as open greenspace that is allowed to flood.
- Access and escape:
 - Safe access and escape routes must be available at times of flood. This does not appear to be possible at this site.

3 Flood risk from surface water

3.1 Existing risk

The NaFRA2 Risk of Flooding from Surface Water (RoFSW) mapping received a significant update and was published January 2025, including for surface water flood extents and depths. However, at the time of writing, the EA has confirmed that the depth information available is not structured in a way that is suitable for planning purposes. Therefore, this Level 2 SFRA considers the third generation RoFSW depth and hazard mapping in addition to the NaFRA2 extents, as agreed with the EA. Surface water depth and hazard should be modelled at the site-specific FRA stage.

3.1.1 Risk of Flooding from Surface Water - NaFRA2 extents

Based on the EA's national scale RoFSW map, as updated in January 2025, surface water risk to the site is predominantly very low. However, given the site is almost wholly at fluvial risk, the surface water risk becomes negligible.

Table 3-1: Existing surface water flood risk based on percentage area at risk using the NaFRA2 RoFSW map

Very low risk (% area)	Low risk (% area)	Medium risk (% area)	High risk (% area)
74	12	4	10




Figure 3-1: Surface water flood extents (NaFRA2 - Risk of Flooding from Surface Water map)

3.1.2 Risk of Flooding from Surface Water - third generation depths and hazard

The EA's national scale third generation RoFSW map shows a significant reduction in surface water risk compared to NaFRA2, therefore the depth and hazard mapping may not be fully representative of potential risk. See Figures 3-2 and 3-3.




Figure 3-2: Medium risk event surface water flood depths (Third generation - Risk of Flooding from Surface Water map)

3.2 Impacts from climate change

Based on the information available, it is predicted that the existing areas of risk will increase in size though the third generation map depths and hazards remain shallow and low respectively.

Site CfS 276 - Huntingdon Racecourse



Figure 3-4: Low risk event surface water flood extent, as a proxy for the medium risk event plus climate change (NaFRA2 - Risk of Flooding from Surface Water map)




Figure 3-5: Low risk event surface water flood depths, as a proxy for the medium risk event plus climate change (Third generation - Risk of Flooding from Surface Water map)




Figure 3-6: Low risk event surface water flood hazard, as a proxy for the medium risk event plus climate change (Third generation - Risk of Flooding from Surface Water map)

3.3 Observations, mitigation options, site suitability, sequential approach to development management - surface water

- The majority of the site is at fluvial flood risk, therefore the surface water risk is negligible.
- The effects of climate change on surface water have not been modelled for this SFRA, however the low risk surface water event has been used as a proxy for the medium risk event plus climate change. Risk is largely similar to the medium risk event, with a greater extent of ponding.
- The site should not be developed, based on the fluvial flood risk.
- The RoFSW map is not suitable for identifying whether an individual property will flood and is therefore indicative. The RoFSW map is not appropriate to act as the sole evidence for any specific planning or regulatory decision or assessment of risk in relation to flooding at any scale without further supporting studies, modelling, or evidence.

4 Cumulative impacts assessment and high risk catchments

4.1 Level 1 cumulative impacts assessment

A cumulative impact assessment was completed through the Huntingdonshire Level 1 SFRA (2024), which aimed to identify catchments sensitive to the cumulative impact of new development. This site is located within one catchment, namely, the Alconbury and Brampton Brooks catchment. This catchment is ranked as high sensitivity. Planning considerations for sites at high sensitivity to the cumulative impacts of development can be found in Appendix G of the Level 1 SFRA. Cumulative impacts of development should also be considered as part of a site-specific FRA.

5 Groundwater, geology, soils, SuDS suitability

Risk of groundwater emergence is assessed in this SFRA using JBA's 5m Groundwater Emergence Map. This dataset is recommended for use by the EA in the SFRA Good Practice Guide³. Figure 5-1 shows the map covering this site and the surrounding areas. Table 5-1 explains the risk classifications.




Figure 5-1: JBA 5m Groundwater Emergence Map

The majority of the site is shown to be at no risk from groundwater emergence. Infiltration SuDS should therefore be appropriate in the majority of the site. Groundwater conditions in the area along the northeastern boundary should be investigated. Ground survey and percolation testing in wet and dry weather conditions may be required.

³ [Strategic flood risk assessment good practice guide. ADEPT. December 2021.](#)

Table 5-1: Groundwater Hazard Classification

Groundwater head difference (m)*	Class label
0 to 0.025	Groundwater levels are either at very near (within 0.025m of) the ground surface in the 100-year return period flood event. Within this zone there is a risk of groundwater flooding to both surface and subsurface assets. Groundwater may emerge at significant rates and has the capacity to flow overland and/or pond within any topographic low spots.
0.025 to 0.5	Groundwater levels are between 0.025m and 0.5m below the ground surface in the 100-year return period flood event. Within this zone there is a risk of groundwater flooding to surface and subsurface assets. There is the possibility of groundwater emerging at the surface locally.
0.5 to 5	Groundwater levels are between 0.5m and 5m below the ground surface in the 100-year return period flood event There is a risk of flooding to subsurface assets, but surface manifestation of groundwater is unlikely.
>5	Groundwater levels are at least 5m below the ground surface in the 100-year return period flood event. Flooding from groundwater is not likely.
N/A	No risk. This zone is deemed as having a negligible risk from groundwater flooding due to the nature of the local geological deposits.
*Difference is defined as ground surface in mAOD minus modelled groundwater table in mAOD.	




Figure 5-2: Soils and geology

6 Residual risk

Although a site may be afforded some protection from defences and / or drainage infrastructure, there is always a residual risk of flooding from asset failure i.e. breaching / overtopping of flood defences, blockages of culverts or drainage assets.

6.1 Potential blockage / breach

There are several culverts around the site where residual risk from potential blockages could impact the site. However, existing risk is significant, therefore residual risk from culvert blockages is negligible.

6.2 Flood risk from reservoirs

The EA's Reservoir Flood Maps (RFM) (2021) show where water may go in the unlikely event of a reservoir or dam failure. Figure 6-1 shows the RFM in a 'dry day' and 'wet day' scenario. A 'dry day' scenario assumes that the water level in the reservoir is the same as the spillway level or the underside of the roof for a service reservoir and the watercourses upstream and downstream of the reservoir are at a normal level. A 'wet day' scenario assumes a worst-case scenario where a reservoir releases water held on a 'wet day' when local rivers have already overflowed their banks.

Virtually the whole site is modelled to be at risk from reservoir flooding.

The EA's SFRA guidance states that where a proposed development site is shown to be at potential risk from reservoir failure, then an assessment into whether the reservoir design or maintenance schedule needs improving should be carried out. Expert advice may be required from an all-reservoirs panel engineer. The Council should consult X to ascertain whether the proposed development could affect the reservoir's risk designation, its design category or how it is operated. The Council, as category 1 responders, can access more detailed information about reservoir risk and reservoir owners using the [Resilience Direct](#) system.




Figure 6-1: EA Reservoir Flood Map

7 Overall site assessment

7.1 Can part b) of the exception test be passed?

This site is not required to pass part b) of the exception test as it is proposed for less vulnerable uses. However, it must still be proven that the development can be safe for its lifetime, which is 75 years for non-residential development.

7.2 Recommendations summary

Based on the evidence presented in the Level 1 SFRA (2024) and this Level 2 SFRA:

- This site should not be developed for less vulnerable uses given the significant risk, as shown in this SFRA.

8 Licencing


To cover all figures within this report:

- Contains Environment Agency information © Environment Agency and/or database right [2025]
- Contains public sector information licensed under the Open Government Licence v3.0. © Crown copyright and database rights [2025]
- HDC Ordnance Survey licence number: 100022322 [2025]
- © 2021 Esri, Maxar, Earthstar Geographics, USDA FSA, USGS, Aerogrid, IGN, IGP, and the GIS User Community

Our Offices

Bristol
Coleshill
Cork
Doncaster
Dublin
Edinburgh
Exeter
Glasgow
Haywards Heath
Leeds
Limerick

Newcastle
Newport
Peterborough
Portsmouth
Saltaire
Skipton
Tadcaster
Thirsk
Wallingford
Warrington



Registered Office

1 Broughton Park
Old Lane North
Broughton
SKIPTON
North Yorkshire
BD23 3FD
United Kingdom

+44(0) 1756 799919
info@jbaconsulting.com
www.jbaconsulting.com

Follow us on  

Jeremy Benn
Associates Limited
Registered in
England
3246693

JBA Group Ltd is
certified to
ISO 9001:2015
ISO 14001:2015
ISO 27001:2022
ISO 45001:2018

